Biosolids Building Costs

No Dryer, No Digesters (20% added for Electric, Plumbing & HVAC) (30% added for Engineering & Contingencies)					
Solids Thickener					
Solids Dewatering		Belt Thickener	Volute Thickener	DAF Thickener	Gravity Thickener
	Belt Press	$ 10,823,174.52	$ 10,612,901.13	$ 10,862,501.13	$ 9,433,488.38
	Volute Press	$ 10,877,774.52	$ 10,667,501.13	$ 10,917,101.13	$ 9,488,088.38
	Screw Press	$ 10,627,979.52	$ 10,417,706.13	$ 10,667,306.13	$ 9,238,293.38
With Dryer, No Digesters (20% added fo Electric, Plumbing & HVAC) (30% added for Engineering & Contingencies)					
Solids Thickener					
Solids Dewatering		Belt Thickener	Volute Thickener	DAF Thickener	Gravity Thickener
	Belt Press	$ 16,777,866.12	$ 16,567,592.73	$ 16,817,192.73	$ 15,597,843.98
	Volute Press	$ 16,832,466.12	$ 16,622,192.73	$ 16,871,792.73	$ 15,652,443.98
	Screw Press	$ 16,582,671.12	$ 16,372,397.73	$ 16,621,997.73	$ 15,402,648.98

Additional Costs

Future Primary Digester				
Description	**Unit**	**Quantity**	**Unit Price**	**Total**
Digester Concrete Tank	LS	1	$ 592,863.42	$ 592,863.42
Primary Digester Cover	LS	1	$ 450,000.00	$ 450,000.00
Digester Boiler Heat Exchanger	LS	1	$ 328,000.00	$ 328,000.00
Digester Building Extension	SF	1200	$ 800.00	$ 960,000.00
Painting (digester)	LS	1	$ 150,000.00	$ 150,000.00
Digester Mixers and Safety Equipment	LS	1	$ 350,000.00	$ 350,000.00
Digester Process Piping	LS	1	$ 285,000.00	$ 285,000.00
Sitework	LS	1	$ 66,666.67	$ 66,666.67
Earthwork/Dewatering	LS	1	$ 133,333.33	$ 133,333.33
		Electrical and HVAC (from total)	20%	$ 663,172.68
		Sub Total		$ 3,979,036.11
		Engineering and Contingencies	30%	$ 1,193,710.83
Estimated Total Project Cost				$ 5,172,746.94

Future Secondary Digester				
Description	**Unit**	**Quantity**	**Unit Price**	**Total**
Digester Concrete Tank	LS	1	$ 592,863.42	$ 592,863.42
Secondary Digester Cover	LS	1	$ 800,000.00	$ 800,000.00
Digester Mixers and Safety Equipment	LS	1	$ 350,000.00	$ 350,000.00
		Electrical and HVAC (from total)	20%	$ 348,572.68
		Sub Total		$ 2,091,436.11
		Engineering and Contingencies	30%	$ 627,430.83
Estimated Total Project Cost				$ 2,718,866.94